

Sub-divisions, T. 2 N., R. 33 E.

Chains	
	East on random between Secs. 12 & 13. Var. 21° East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.10	Intersected N & S line 25 links S of corner. S. 89° 50' W. on true line.
40.05	Set post and made earth mound for $\frac{1}{4}$ Sec. corner.
73.50	Brook, 10 lks., flows N.E.
80.10	To corner. Land, level. Soil, 1st rate. Good grass.
	North between Secs. 11 & 12 .
1.50	Wagon road, E & W.
2.50	Brook, 10 links, flows N W.
37.00	Enter river bottom.
40.00	Set post for $\frac{1}{4}$ Sec. corner from which A Cottonwood, 15 ins. diam. bears S.75 W.46 lks.
63.50	Umatilla River, 2 chs. wide, flows N 20 W.
80.00	Set stone 20 x 15 x 12 for corner to Secs. 1, 2, 11, 12. Land, level. Soil, 2d rate bottom. Subject to inundations.
	East on random between Secs. 1 & 12. Var. 21° East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.80	Intersected N & S line 50 N of corner. N 89° 38' W on true line.
21.50	Enter field, N & S.
39.90	Set post and earth mound for $\frac{1}{4}$ Sec. corner.
61.50	Leave field.
79.80	To corner. Land, level. Soil, 1st rate.