

Subdivisions, T. 2 N. R. 33 E.

Chains

North on random between Secs. 1 & 2.

40.00 Set temporary $\frac{1}{4}$ Sec. corner.

80.20 Intersected North boundary 25 E. of Corner.

S.00°10' E. on true line.

40.20 Set stone 18 x 12 x 10 for $\frac{1}{4}$ Sec. corner in river bottom.

80.20 To Corner.

Land, level.

Soil, 1st rate.

May 23, 1871.

North between Secs. 34 & 35.

40.00 Set stone 15 x 12 x 10 for $\frac{1}{4}$ Sec. corner.

80.00 Set stone 18 x 15 x 10 for corner to Secs. 34, 35, 26 & 27.

Land, level.

Soil, 1st rate.

East on random between Secs. 26 & 35.

Var. 21° East.

40.00 Set temporary $\frac{1}{4}$ Sec. corner.

80.14 Intersected N & S line 21 S. of post

S. 89° 51' W. on true line.

40.07 Set post and made earth mound for $\frac{1}{4}$ Sec. Corner.

80.14 To corner.

Land, level.

Soil, 1st rate.

North between Secs. 26 & 27.

40.00 Set post and made earth mound for $\frac{1}{4}$ Sec. corner.

80.00 Set post and made earth mound for corner to Secs. 26, 27,
22, 23.

Land, level.

Soil, 1st rate.

East on random between Secs. 23 & 26.

Var. 21° East.