

Subdivisions, T. 2 N. R. 33 E.

| Chains | |
|--------|---|
| 40.00 | Set temporary $\frac{1}{4}$ Sec. corner. |
| 79.94 | Intersected N & S line 16 S. of corner. |
| | S. $89^{\circ} 53'$ W. on true line. |
| 39.97 | Set post and made mound of earth for $\frac{1}{4}$ Sec. corner. |
| 79.94 | To corner. |
| | Land, level. |
| | Soil, 1st & 2d rate. |
| <hr/> | |
| | North between Secs. 22 & 23. |
| 40.00 | Set post and made earth mound for $\frac{1}{4}$ Sec. corner. |
| 80.00 | Set post and raised earth mound for corner to Secs. 22, |
| | 23, 14 & 15. |
| | Land, level. |
| | Soil, 1st rate. |
| <hr/> | |
| | East on random between Secs. 14 & 23. |
| | Var. $21^{\circ}30'$ East. |
| 40.00 | Set temporary $\frac{1}{4}$ Sec. corner. |
| 79.92 | Intersected N & S line 10 N. of Cor. |
| | N. $89^{\circ} 56'$ W. on true line. |
| 39.96 | Set post and made mound of earth for $\frac{1}{4}$ Sec. corner. |
| 79.92 | To Corner. |
| | Land, level. |
| | Soil, 1st rate. |
| <hr/> | |
| | North between Secs. 14 & 15. |
| 30.00 | LaGrand & Pendleton road, course NW & SE. |
| 40.00 | Set post and made mound of earth for $\frac{1}{4}$ Sec. corner. |
| 80.00 | Set post and made mound of earth for corner to Secs. 14, |
| | 15, 10 & 11. |
| | Land, $N\frac{1}{2}$ rolling; $S\frac{1}{2}$, level. |
| | Soil, 1st & 2nd rate. |
| <hr/> | |
| | East on random between Secs. 11 & 14. |
| | Var. 20° East. |