

Subdivisions, T. 2 N. R. 33 E.

Chains	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.96	Intersected N & S line 14 N. of corner N.89°54' W. on true line.
39.98	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
79.96	To corner. Land, level. Soil, 2nd rate.
North between Secs. 10 & 11.	
10.00	Wagon road, E & W.
35.00	Enter field.
40.00	Set stone 18 x 15 x 8 for $\frac{1}{4}$ Sec. corner.
52.50	Leave field.
63.00	Umatilla river, N.W.
80.00	Set post corner to Secs. 10,11, 2 & 3, from which An Alder 10 dia. bears N.75 W-43 links A Balm 15 " " S.80 W-30 " Land, level. Soil, 1st rate in field.
East on random between Secs. 2 & 11. Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.10	Intersected N & S line 12 lks. S. of corner. S.89° 55' W. on true line.
23.50	Enter field.
30.00	Leave field.
40.05	Set post and made stone mound $\frac{1}{4}$ S. cor.
80.10	To corner.
North on random between Secs. 2 & 3.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.54	Intersected North line 21 E. of corner. S. 00° 9' E. on true line.
40.54	Set stone 14 x 12 x 10 for $\frac{1}{4}$ Sec. corner.