

Subdivisions, T. 2 N. R. 33 E.

Chains

80.18

To corner.

Land, level.

Soil, 1st rate.

May 25, 1871.

North bet. Secs. 32 & 33.

40.00

Set post and raised mound of earth for $\frac{1}{4}$ Sec. corner.

80.00

Set post and made mound of earth for corner to Secs.

32, 33, 28 & 29.

Land, level.

Soil, 1st rate.

East on random between Secs. 28 & 33.

Var. 21° East.

40.00

Set temporary $\frac{1}{4}$ Sec. corner.

79.84

Intersected N & S line 34 links S. of corner.

S. 89° 44' W. on true line.

2.00

Tudie Willow 10 links, flows N.

39.92

Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.

79.84

To corner.

Land, level.

Soil, 1st rate.

North between Secs. 28 & 29.

40.00

Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.

62.00

Tudie Willow, 10 links, flows N.W.

80.00

Set post and made mound of earth for corner to Secs.

28, 29, 20 & 21.

Land, level.

Soil, 2nd rate.

East on random between Secs. 21 & 28.

Var. 21° East.

40.00

Set temporary $\frac{1}{4}$ Sec. corner.

80.00

Intersected N & S line 28 links S. of corner.