

Subdivisions, T. 2 N. R. 33 E.

Chains

40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.40	Intersected N & S line 24 lks. S. of corner. S. 89° 50' W. on true line.
39.70	Set post and made stone mound for $\frac{1}{4}$ Sec. corner.
79.40	To corner. Land, level. Soil, 1st rate.
North between Secs. 8 & 9.	
17.50	Wagon road. Course E & W.
40.00	Set stone 14 x 14 x 8 for $\frac{1}{4}$ Section corner.
72.50	Umatilla river, 2 chains wide, flows W.
80.00	Set stone 18 x 14 x 9 for corner to Secs. 8, 9, 4, 5. Land, generally level. Soil, 2d rate on river. Timber, Cottonwood.
East on random between Secs. 4 & 9. Variation 21° 30' East.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.10	Intersected N & S line 32 lks. S. of corner. S. 89° 47' W. on true line.
35.00	Enter Indian field.
40.05	Set stone 18 x 12 x 8 for $\frac{1}{4}$ Sec. corner.
50.00	Leave field.
80.10	To corner. Land, gravelly. Soil, 2d rate.
North on random between Secs. 4 & 5.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.20	Intersected North boundary 14 links E. of corner. S. 00° 01' E. on true line.
40.20	Set post and made mound for $\frac{1}{4}$ Sec. corner.
80.20	To corner.