

Allotments, T. 2 N. R. 33 E.

Chains	
	Thence
	North on W. bdy. of Sec. 13.
80.00	To post cor. for cor. to Secs. 13, 14, 11, 12.
	Thence
	East on random on N. bdy. of Sec. 13.
80.12	Intersected East bdy. of Sec. 13, 24 lks. S. of Sec. cor. S. 89° 50' W. on true line.
10.00	Set post and made earth mound for 1/32 S. cor.
20.00	Set stone 17 x 10 x 5 for 1/16 S. corner.
30.00	Set post and made mound of earth for 1/32 Sec. cor.
40.01	To $\frac{1}{4}$ Sec. corner.
	Thence
	North from $\frac{1}{4}$ Sec. cor. to the $\frac{1}{4}$ Sec. cor. on North boundary of Sec. 12.
80.00	Intersected North boundary of Sec. 12 at $\frac{1}{4}$ Sec. cor. S. on true line.
20.00	Set post and made mound of earth for 1/16 Sec. corner.
33.00	To Umatilla river.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
60.00	Set post and made mound of earth for 1/16 Sec. corner.
80.00	To the $\frac{1}{4}$ Sec. cor. on S. bdy. of Sec. 12.
	Thence
	West on North boundary of Sec. 13.
50.00	Set post and made earth mound for 1/32 S. corner.
60.00	Set stone 10 x 10 x 7 for 1/16 Sec. corner.
70.00	Set post and made mound of earth for 1/32 S. corner.
73.45	To dry branch.
80.12	To Sec. corner.
	The land in this section is level. Soil, 1st rate. A good growth of grass.
	North on West bdy. of Sec. 12.
2.00	Wagon road.
2.54	Dry bed of stream.
20.00	Set post and made earth mound for 1/16 Sec. corner.