

Chains	
	E. on random from 1/16 S. corner to 1/16 Sec. corner on E. bdy of Sec. in N.E. Qr. of Section.
80.06	Intersected N & S line at corner. W. on true line.
9.00	Umatilla River, 2 chs.
10.00	Set post in stone mound for 1/32 S. corner.
20.00	Set post in stone mound for 1/16 S. corner.
30.00	Set post in stone mound for 1/32 S. corner.
40.03	To 1/16 S. corner.
50.00	Set post in stone mound for 1/32 S. corner.
60.00	Set post in stone mound for 1/16 S. corner.
70.00	Set post in stone mound for 1/32 S. corner.
74.32	Umatilla River, 2.50 links.
80.06	To 1/16 Sec. corner. Thence North on W. bdy. of Sec. 11.
63.00	Umatilla River.
80.00	To Section cor. Thence East on North bdy of Sec. 11.
80.10	Intersected N & S line 14 lks. S. of cor. S. 89° 55' W. on true line.
10.00	Set stone 12 x 10 x 6 for 1/32 S. corner.
20.00	Set post for 1/16 S. corner.
23.10	Enter Indian field.
30.00	Set stone 17 x 10 x 7 for 1/32 Sec. corner.
30.00	Leave field.
40.05	To $\frac{1}{4}$ Sec. corner. Thence North from $\frac{1}{4}$ S. corner to $\frac{1}{4}$ S. corner on N. bdy of Sec. 2.
80.24	Intersected N. bdy of Section 2 at $\frac{1}{4}$ Sec. corner. South on true line.
20.00	Set post for 1/16 Sec. corner.
40.24	Set temporary $\frac{1}{4}$ Sec. corner.
60.24	Set stone 14 x 12 x 7 for 1/16 S. corner.