

Allotments, T. 2 N.R. 33 E.

Chains	
60.00	Set post in earth mound for 1/16 Section corner.
80.20	To $\frac{1}{4}$ Section corner on South boundary of Section 4. West on North boundary of Sec. 9.
50.00	Set post in earth mound for 1/32 Sec. corner. Agency buildings are due South from this point about 10.00 chains.
60.00	Set post in stone mound for 1/16 Sec. corner.
70.00	" " " " " " 1/32 " "
80.10	To corner. North on W. boundary of Sec. 4.
20.00	Set post in earth mound for 1/16 Sec. corner. East on random from 1/16 Section corner in S.W.Qr. of Sec. 4 to 1/16 Sec. corner in S. E. Qr. of Sec. 4.
80.04	Intersect E. boundary of Sec. 4 at 1/16 Section corner. West on true line.
8.00	Enter Alex McKay's field.
10.00	Set post in stone mound for 1/32 Sec. corner.
20.00	" " " " " " 1/16 " "
28.50	Enter Alex McKay's meadow.
30.00	Set stone 14 x 10 x 9 for 1/32 Section corner.
39.50	Leave A. McKay's meadow.
40.04	To $\frac{1}{16}$ Section corner.
50.00	Set post in stone mound for 1/32 Sec. corner.
60.00	Set stone 12 x 10 x 9 for 1/16 Sec. corner. Made rock md.
70.00	" " 14 x 10 x 7 " 1/32 " "
80.04	To 1/16 Section corner. Thence North on West boundary of Section 4.
40.00	To $\frac{1}{4}$ Section corner. Thence East on random from $\frac{1}{4}$ Qr. corner on West boundary of Sec. 4 to the $\frac{1}{4}$ Sec. boundary on East boundary of Sec. 4.
80.00	Intersect E. boundary of Sec. 4 at $\frac{1}{4}$ Section corner. West on true line.
10.00	Set post in earth mound for 1/32 Section corner.