

Allotments, T. 2 N. R. 33 E.

Chains	
	The land in Sec. 8 on the Umatilla River is good for agricultural purposes.
	North on W. boundary of Section 5.
10.20	To Umatilla River.
20.00	Set post in earth mound for 1/16 Sec. corner.
	East from 1/16 Sec. corner in S.W. Qr. of Sec. 5 to 1/16 Sec. corner in S. E. Qr. of Sec. 5.
80.06	Intersected E. boundary of Sec. 5 at 1/16 S. corner.
	West on true line.
4.00	Enter field.
7.00	Indian house.
10.00	Set post for 1/32 Sec. corner.
19.00	Leave Indian field.
20.00	Set post for 1/16 S. corner.
30.00	" " " 1/32 " "
40.00	To 1/16 Sec. corner.
50.00	Set post for 1/32 S. corner.
60.00	" " " 1/16 " "
70.00	" " " 1/32 " "
80.06	To 1/16 Sec. corner in S.W. Qr.
	Thence
	North on W. boundary of Sec. 5.
40.00	To 1/4 S. corner.
	Thence
	East from 1/4 Sec. corner in W. boundary of Sec. 5 to 1/4 Sec. corner in E. boundary of Section 5.
80.00	Intersected E. boundary of Sec. 5, 18 links S. of 1/4 Sec. corner.
	S. 89° 52' West on true line.
10.00	Set post in earth mound for 1/32 S. corner.
20.00	" " " " " " 1/16 " "
30.00	" " " " " " 1/32 " "
40.00	" " " " " " 1/4 " "
50.00	" " " " " " 1/32 " "