

Allotments, T. 2 N., R. 33 E.

Chains	
79.80	To 1/16 Section corner on W. boundary of Sec. 7.
	Thence
	North on W. boundary of Sec. 7.
67.00	Umatilla River.
80.00	To Section corner.
	Thence
	East on N. boundary of Sec. 7.
79.54	Intersected E. boundary at corner.
	W. on true line.
10.00	Set post in earth mound for 1/32 Section corner.
20.00	" " " " " " 1/16 " "
30.00	" " " " " " 1/32 " "
40.00	To 1/4 Sec. corner.
	Thence
	North from 1/4 Sec. corner on S. boundary of Sec. 6 to
	1/4 Sec. corner on N. boundary of Sec. 6.
80.60	Intersected N. boundary of Sec. 6 at $\frac{1}{2}$ Sec. corner.
	S. on true line.
20.60	Set post for 1/16 Section corner.
40.60	" temporary 1/4 Section corner.
60.60	" post for 1/16 Section corner.
71.00	Umatilla River.
80.60	To 1/4 S. corner on S. boundary of Section 6.
	Thence
	West on N. boundary of Section 7.
49.00	Umatilla River:
50.00	Set post in earth mound for 1/32 S. corner.
60.00	" " " " " " 1/16 " "
70.00	" " " " " " 1/32 " "
79.54	To Section corner.
	The land in Sec. 7 is good for farming.
	North on W. boundary of Sec. 6.
20.00	Set post in stone mound for 1/16 S. corner.
	Thence
	East from 1/16 Sec. corner in S. W. Qr. of Sec. 6 to 1/16