

Allotments, T. 2 N. R. 33 E.

Section 8.

Chains	From the 1/16 Sec. corner, 30 chains N of 1/4 Sec. corner, between Secs. 7 & 8, I run
79.60	<p>S. 89° 53' E. on random line in Sec. 8.</p> <p style="text-align: right;">Variation 20° East.</p> <p>Setting temporary corner at every 20, 40 & 60 chs. and at</p> <p>Intersect the N & S line, 50 lks. S. of 1/16 Sec. corner</p> <p>30 chains N of 1/4 Sec. corner between Secs. 8 & 9.</p>
19.90	<p>Thence, I run</p> <p>S. 89° 46' W. on true line in Sec. 8.</p> <p style="text-align: right;">Variation 21° 30' East.</p> <p>Set basalt stone 10 x 9 x 7 ins., 6 ins. in the ground for 1/4 Sec. corner, marked 1/16 on N. face and raised a mound of stone over it. from which</p>
39.80	<p>A balm 30 ins. diam. bears W. 39 links distant, marked 1/16 S.B.T.</p> <p>River, 100 links North, runs W. through brush and timber.</p> <p>Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 Sec. corner, marked 1/16 on N. face. Dug pits 18 x 18 x 12 ins. E & W of stone 5 1/2 ft. distant, and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.</p>
59.70	<p>Set basalt stone 10 x 8 x 8 ins., 6 ins. in the ground for 1/16 Sec. corner, marked 1/16 on N. face, and raised a mound of stone over it. Pits impracticable.</p>
65.00	<p>Fence, course N.E.</p>
79.60	<p>To the 1/16 Sec. corner, 30 chains N. of 1/4 Sec. corner between Secs. 7 & 8.</p> <p>Land, level. Timber and Brush.</p> <p>Soil, 1st rate.</p>
79.60	<hr/> <p>From the 1/16 Sec. corner, 10 chains North of 1/4 Sec. corner, between Secs. 7 & 8, I run</p> <p>East on random line through Sec. 8.</p> <p style="text-align: right;">Var. 21° East.</p> <p>Setting temporary corner at every 20, 40 and 60 chains and at</p> <p>Intersect the N & S line 40 links S. of 1/16 Sec. corner,</p>