

Allotments, T. 2 N., R. 33 East

Chains	
7.00	Railroad, course N.85° W.
10.00	<p>Set post 3 ft. long, 3 ins. square with marked stone 12 ins. in the ground for 1/32 Sec. cor., marked 1/32 S. on W. face; dug pits 18x18x12 ins., N & S of post 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base around post.</p> <p>Land, rolling. Soil, 1st rate.</p>
	<p>From the ¼ Sec. cor., between Secs. 10 & 11, which is a basalt stone 10x8x7 ins., 6 ins. in the ground marked ¼ on N face with pits 18x18x12 ins. N & S of stone, 5½ ft. distant and mound of earth 1½ ft. high, 3½ ft. base over it</p> <p style="text-align: center;">I run</p> <p>North on true line between Secs. 10 & 11.</p> <p style="text-align: right;">Var. 20° East.</p> <p>Through grain.</p>
10.00	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/32 Sec. cor., marked 1/32 S. on W. face; dug pits 18x18x12 ins. N & S of post 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base around post.</p> <p>Grain field, rolling and rich. July 1st, 1889.</p>
39.80	<p>From the 1/32 Sec. corner, 10 chains N of ¼ Sec. corner between Secs. 10 & 11, I run</p> <p>East on random line in Sec. 11. Var. 20° East.</p> <p>Setting temporary corner at 20 chains and at</p> <p>Intersected the 1/32 Sec. corner, 10 chains N of ¼ Sec. cor., 10 chs. N. of ¼ Sec. cor. in center of Sec. 11 at post.</p> <p style="text-align: center;">Thence, I run</p> <p>West on true line in Sec. 11. Var. 20° 15' East.</p>
4.00	Road, course N. 80° West.
19.90	<p>Set basalt stone 11x9x8 ins. 7 ins. in ground for 1/32 Sec. cor., marked 1/32 on W face and raised mound of stone</p>