

Chains	Section 36.
	<p>From the 1/16 Sec. corner 20 chains S. of the corner to Secs. 25, 26, 35 &amp; 36, which is a charred stake, 12 ins. in the ground with pits 18 x 18 x 12 ins. N &amp; S. of stake 5½ ft. distant and mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit a stake 2 ins. square firmly set in the ground, marked 1/16 S. on W. face.</p> <p>I run, East on true line in Sec. 36.</p> <p>Variation 19½° East.</p>
17.50	<p>Gulch, course N.W. Dry bed of creek.</p>
20.00	<p>Set stone 10 x 12 x 8 ins., 8 ins. in the ground for 1/32 Sec. corner, marked 1/32 on N. face; dug pits 18x18x12 E &amp; W of stone 5½ ft. distant; raised a mound of earth 1½ ft high, 3½ ft. base over it.</p> <p>Land, mouth of canyon. Soil, 1st rate. Good grass.</p> <p>From the 1/32 Sec. corner, 20 chains S. and 20 chains E. of the corner to Secs. 25, 26, 35 &amp; 36.</p> <p>I run South on true line in Sec. 36.</p> <p>Variation 19° East.</p> <p>Descend.</p>
10.00	<p>Set stone 15 x 8 x 6 ins., 10 ins. in the ground for 1/32 Sec. corner, marked 1/32 on W. face, raised a mound of stone over it. Pits impracticable.</p> <p>Land, mouth of canyon. Soil. 1st rate. Grass, good.</p> <p>From the 1/16 Sec. corner, 20 chains S. of the corner to Secs. 25, 26, 35 &amp; 36.</p> <p>I run South on true line between Secs. 35 &amp; 36.</p> <p>Variation 19° 15' East.</p> <p>Ascend.</p>
10.00	<p>Set stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/32 Sec. corner, marked 1/32 on W. face; dug pits 18x18x12</p>