

T. 3 N. R. 33 E.

South boundary

| Chains | |
|--|--|
| 75.55 | <p>Set a post 48 x 14 x 4 ins., 12 ins. in the ground for cor. to secs. 5, 6, 31 & 32, marked T. 3 N.S.31 on N.W. R.33 E. S. 32 on N.E., T. 2 N. Sec. 5 on S.E., S. 6 on S.W.. 5 notches on E. and 1 notch on W. edges. Dug pits 18 x 18 x 12 ins. in each sec., 5½ ft. distant, raised a mound of earth 2 ft. high, 4½ ft. base around post.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate. Poor grass.</p> <p style="text-align: right;">August 13, 1887</p> |
| <hr/> <p style="text-align: center;">South 89° 46' E. between secs. 5 & 32. Variation 21° 30' East</p> | |
| 4.25 | Gulch, course S. |
| 40.00 | <p>Set a basalt stone 10 x 8 x 6 ins., 6 ins. in the ground for ¼ Sec. corner, marked ¼ on W. face. Dug pits 18 x 18 x 12 ins. E & W. of corner 5½ ft. distant, raised a mound of earth 1½ ft. high, 3½ ft. base along side.</p> |
| 58.00 | Road. |
| 63.90 | Small gulch, course S.W. |
| 80.00 | <p>Set a basalt stone 10 x 8 x 7 ins., 6 ins. in the ground for corner to Secs. 4 & 5, 32 & 33, marked T. 3 N. S. 33 on N.E., T. 2 N. S. 4 on S.E., R. 33 E. S. 5 on S.W., S. 32 on N.W. faces with 4 notches on E. and 2 notches on W. edges. Dug pits 18 x 18 x 12 ins. in each sec. 5½ ft. dist., and raised a mound of earth 2 ft. high, 4½ ft. base alongside.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate. Poor grass.</p> |
| <hr/> <p style="text-align: center;">South 89° 46' E. bet. Secs. 4 & 33. Variation 21° East.</p> | |
| 14.50 | Gulch, course S.W. |
| 24.75 | " " " " |

-50