

N. bdy. T. 1 , N., R. 33 E.
(S. bdy. T. 2 N.R. 33 E.)

Chains 20.00	Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E&W of cor., 5½ ft. distant; raised md. of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.
26.20	Trail, course N.
28.00	Tudie Willow Creek, dry. Course N.
40.00	Set a basalt stone 12x9x9 ins., 8 ins. in the ground for ¼ secs. cor., marked ¼ on N. face; dug pits 18x18x12 ins. E & W of corner, 5½ ft. distant; raised earth mound 1½ ft. high, 3½ ft. base alongside.
43.50	Trail, course N & S.
51.50	Wagon road, course N.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18x18x12 ins. E & W of cor. 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face .
80.00	Set a basalt stone 12x9x9 ins., 8 ins. in the ground for cor. to Secs. 3, 4, 33 & 34, marked 3 notches on the E & W edges; dug pits 18x18x12 ins. in each sec., 5½ ft. dist.; raised earth mound 2 ft. high, 4½ ft. base alongside. Land, level. Soil, 2nd rate. Good grass. No timber.
<hr/>	
North 89°57' E. on N. boundary Sec. 3. Var. 19° East.	
20.00	Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. E&W of cor. 5½ ft. distant; raised md. of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
37.00	Indian Trail NW & SE.
40.00	Set a basalt stone 18x10x8 ins. 15 ins. in the ground for ¼ sec. cor., marked ¼ on N face; dug pits 18x18x12 ins. E&W of corner, 5½ ft. distant; raised earth mound alongside 1½ ft. high, 3½ ft. base.
43.10	Tudie Willow Creek, dry, N.W.
51.50	Wagon road, course N & S.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18x18x12 ins. E & W of cor. 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base