

N. bdy. T. 1, N., R. 33 East.  
(S. bdy T.2, N., R. 33 E.)

Chains	over it. In E. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.	
80.00	Set a basalt stone 12x9x9 ins., 8 ins. in the ground for corner to secs. 2,3,34 & 35, marked 4 notches on W. & 2 on E. edges; dug pits 18x18x12 ins. in each sec. 5½ ft. dist.; raised earth md. 2 ft. high, 4½ ft. base alongside.	
	Land, level. Soil, 2nd rate. No timber. Good grass.	
	North 89°57' E. on N. boundary Sec. 2. Var. 21° East.	
10.05	Wagon road, course N.W.	
20.00	" " " N.	
20.00	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. E & W of cor. 5½ ft. dist.; raised a md. of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.	
40.00	Set a basalt stone 18x10x4 ins., 15 ins. in the ground for ¼ Sec. cor.; marked ¼ on N face; dug pits 18x18x12 ins. E & W of cor., 5½ ft. dist.; raised md. of earth alongside.	
48.20	Dry creek, course N.W.	
52.20	" " " S.W.	
57.20	" " " N.W. Ascend.	
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E&W of corner 5½ ft. dist.; raised a md. of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.	
80.00	Set a basalt stone 18x12x10 ins., 14 ins. in the ground for cor. to secs. 1,2,35 & 36, marked 5 notches on W. and 1 on E. edges. Raised a md. of stone alongside. Pits impracticable.	
	Land, mountainous 22.70 chains. Soil, 2nd rate on level land; 4th rate on mountains. No timber. Good grass.	
	N. 89° 57' E. on N. bdy. Sec. 1. Var. 21° 30' East	
13.00	Ridge	+50
18.00	Draw, course S.	-80
40.00	Set a basalt stone 18x12x12 ins. 14 ins. in the ground for ¼ sec. corner, marked ¼ on N. face. Raised mound	+200