

N. Boundary T. 1 N., R. 33 East.

(S. boundary T. 2 N., R. 33 E.)

Chains		
	of stone alongside. Pits impracticable.	
52.00	Summit of ridge.	+50
80.00	To corner to Tps. 1 & 2 N. Rs. 33 & 34 E.	-75
	Land, mountainous 80. chains.	
	Soil, rocky 4th rate.	
	No timber.	
	Good grass.	
	The S.E. $\frac{1}{2}$ of this Township is very rough and broken; but is covered with fine bunch grass. The N.W. $\frac{1}{2}$ is gently rolling. Soil is 1st and 2nd rate and suitable for farming. No timber.	
	August 4th, 1887.	
<p>Field Notes of the Subdivisions of T. 2 N.R. 33 E. Survey by Jas. P. Currin and Jas. Noland, under their Contract, dated May 4, 1887.</p>		
	Beginning at corner to Secs. 35 & 36, T. 2 North R. 33 E. and 1 & 2, T. 1 N. R. 33 E., I ran North between Secs. 35 and 36.	
	Variation 22° East.	
	Ascend.	
10.00	Top of ridge, W.	+400
20.00	Set basalt stone 12 x 8 x 6 ins., 8 ins. in the ground for 1/16 Sec. corner, marked 1/16 on W. face; dug pits 18 x 18 x 12 ins. N and S of stone 5 $\frac{1}{2}$ ft. distant; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.	
	Descend.	
29.50	Gulch, West.	-300
	Ascend gradual slope.	
38.00	Summit ridge.	+200
	Descend gradual slope.	
40.00	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. corner marked $\frac{1}{4}$ on W. face; dug pits 18x18x12 ins. N & S of stone 5 $\frac{1}{2}$ ft. distant. Raised	