

Subdivisions, T. 2 N., R. 33 E.

Chains		
34.35	Enter field E & W.	
39.55	Leave same.	
40.00	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on W face; dug pits 18 x 18 x 12 ins. N and S of post $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
41.80	Dry ditch N.W. Ascend.	-20
60.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked $\frac{1}{16}$ S on W face.	
64.55	Wagon road E & W.	
80.00	Set basalt stone 10 x 8 x 7 ins., 6 ins. in the ground for cor. to secs. 11, 12, 13 and 14, marked with 4 notches on S and 1 notch on E. edges; dug pits 18 x 18 x 12 ins. in each sec. $5\frac{1}{2}$ ft. dist.; raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Land, gently rolling. Soil, 1st rate, partly cultivated.	
79.80	East on random line between Secs. 12 & 13. Variation $20^{\circ} 10'$ East. Set temporary cors. at 20, 40 and 60 chains and at Intersect E bdy. Township 5 lks. N of cor. to secs. 12, 13, 7 & 18.	
19.95	Thence N $89^{\circ} 58'$ W on true line. Variation $20-3/4^{\circ}$ East. Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ Sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake $5\frac{1}{2}$ ft. dist.; raised mound of stone and earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked $\frac{1}{16}$ S on N face.	