

Chains	
11.50	Ditch N.W.
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. E and W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
39.90	Deposited charred stake 12 ins. in the ground for ¼ Sec. cor.; dug pits 18x18x12 ins. E & W of cor. 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked ¼ S on N face.
46.50	Wagon road N.E.
55.00	Enter plowed field N & S.
59.85	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. E & W of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.
60.75	Leave plowed field N & S.
71.00	Trail N.
79.80	Cor. to secs. 26, 27, 34 and 35. Land, mostly level. Soil, 2nd rate. Considerable alkali.
<hr/> North between secs. 26 and 27. <div style="text-align: right;">Var. 20° East.</div>	
4.00	Dry bed of creek N.W.
15.25	Dry bed of creek N.W.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. N & S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on W face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ Sec. cor.; dug pits 18x18x12 ins. N & S of stake 5½ ft. dist.