

## Subdivisions, T. 2 N., R. 33 E.

Chains	
	marked 1/4 S. B. T.
59.77	Deposit charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. E & W of stake, 5 1/2 ft. dist. raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
79.00	Spring branch 55 links N.W.
79.70	Cor. to secs. 2, 3, 10 and 11. Land, level. Soil, sandy, 2nd rate. Dense brush cottonwood 79.70 chs. Alder and thorns.
<hr/>	
	North on random between Secs. 2 & 3. Variation 20° East: Set temporary cors. at 20, 40 and 60 chains and at 75.84 Intersect N. bdry Township 40 lks E. of cor. to secs. 2, 3, 34 and 35. Thence; S. 17' E. on true line. Variation 21° East.
15.84	Set post 3 ft. long 3 ins. square 24 ins. in the ground for 1/16 sec. cor. marked 1/16 S on W face; dug pits 18x18x12 ins. N and S of cor. 5 1/2 ft. dist.; raised mound of stone and earth 1 1/2 ft. high, 3 1/2 ft. base over it.
30.00	Wagon road W.
35.84	Deposited charred stake 12 ins. in the ground for 1/4 sec. cor.; dug pits 18x18x12 ins. N and S of stake 5 1/2 ft. dist., raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in N. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/4 S on W. face.
54.75	Wagon road W.
55.00	Fence and enter field.
55.84	Set post 3 ft. long 3 ins. square 24 ins. in the ground