

Subdivisions, T. 2 N. R. 33 E.

Chains	Thence
	West on true line Variation 20° East.
4.50	Wagon road N & S.
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked 1/16 S on N face.
39.25	Dry ditch W by N.W.
39.90	Set basalt stone 16 x 12 x 8 ins., 10 ins. in the ground for 1/4 sec. corner marked 1/4 on N. face; dug pits 18 x 18 x 12 ins. E & W of stone 5½ ft. dist. and raised mound of stone and earth 1½ ft. high, 3½ ft. base over it.
52.50	Gulch, N.
59.85	Set basalt stone 10 x 9 x 8 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N face; dug pits 18 x 18 x 12 ins. E & W of corner 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.
79.80	Cor. to secs. 21, 22, 27 and 28. Land, rolling. Soil, 1st rate. Bunch grass fair. All good agricultural land.
	North between Secs. 21 and 22. Var. 19° 15' East.
2.64	Wagon road N.E.
20.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S on W face; dug pits 18 x 18 x 12 ins. N and S of post 5½ ft. distant and raised mound of earth 1½ ft. high, 3½ ft. base around it.
34.50	Dry ditch N.W.

-20