

Subdivisions, T. 2 N. , R. 33 E.

Chains	
79.80	<p>over it and in E pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p> <p>Cor. to secs. 9, 10, 15 and 16.</p> <p>Land, rolling, gently sloping to N.</p> <p>Soil, light and ashy, 3rd rate.</p>
20.00	<p>North between secs. 9 and 10.</p> <p style="text-align: right;">Var. $20\frac{1}{2}^{\circ}$ East.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W face.</p>
28.25	Wagon road E and W.
31.75	Brush and edge of bluff 20 ft. high.
33.75	Spring branch 10 lks. runs W.
40.00	<p>Set basalt stone 17 x 8 x 7 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. corner, marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 ins. N and S of stone, $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, from which</p> <p style="padding-left: 40px;">A Balm 10 ins. diam. bears S.40° E., 83 links dist., marked 1/4 S.B.T.</p>
57.55	Railroad runs E & W.
60.00	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. cor., marked 1/16 S on W. face; dug pits 18 x 18 x 12 ins. N & S of post, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.</p>
78.25	Umatilla river 100 lks. S.W.
80.00	<p>Set stone (boulder) 14 x 12 x 10 ins., 9 ins. in the ground for corner to secs. 3, 4, 9 and 10, marked with 5 notches on S and 3 notches on E. edges, from which</p> <p style="padding-left: 40px;">A Willow 14 ins. diam. bears N.80° E 35 lks. dist., marked T2N S3 B.T.</p> <p style="padding-left: 40px;">A Balm 6 ins. diam. bears S10° E. 50 lks. dist.</p>