

Subdivisions, T. 2 N., R. 33 E.

Chains		
	S. 9' East on true line. Variation 21° East.	
15.70	Set basalt stone 10 x 8 x 6 ins., 6 ins. in the ground for 1/16 sec. corner marked 1/16 on W. face; dug pits 18 x 18 x 12 ins. N & S of stone 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it.	
35.20	Canyon S.W.	-100
35.70	Deposited charred stake 12 ins. in the ground for ¼ sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake 5½ ft. distant; raised mound of earth 1/2 ft. high, 3½ ft. base over it, and in N. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground, marked 1/4 S on W face.	
	Ascend.	
43.50	Bluff rock facing S.	+10 ft
48.00	Wagon road E & W.	
49.00	Fence and enter field.	
55.70	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked 1/16 S on W. face.	
56.00	Yard fence and leave field E & W.	
57.50	House bears E. 12 links.	
60.20	House bears E. 50 links.	
63.00	Well, 10 ft. deep.	
65.00	Garden E & W.	
75.70	Cor. to secs. 3, 4, 9 and 10. Land, N½ rolling; South ½, level, fair agricultural land. Soil, 1st rate. Timber: Balm and pine in bottom.	
	North between secs. 32 and 33. Variation 20° East.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16	