

## Subdivisions, T. 2 N., R. 33 E.

Chains	
	N.89° 51' W. on true line. Variation same.
2.00	Tudie Willow Creek S.W.
3.50	House bears S about 200 lks.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake, 5½ ft. distant; raised mound of stone and earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S on N. face.
60.00	Drove charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.00	Cor. to secs. 28, 29, 32 and 33. Land, mostly level. Soil, 2nd rate. Considerable alkali.
	North between secs. 28 and 29. Variation 21° East.
5.00	Wagon road S.W.
<sup>20</sup> <del>80</del> .00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N and S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in the N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.