

## Subdivisions, T. 2 N., R. 33 E.

Chains	
39.80	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on N face.
59.70	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake, $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in ground marked $\frac{1}{16}$ S on N. face.
79.60	Cor. to secs. 16, 17, 20 and 21. Land, mostly level. Soil, 1st rate. Good farming land.
	Aug. 30th, 1887.
	North between secs. 16 and 17.
	Variation $21^{\circ}$ East.
20.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{16}$ S on W. face.
25.50	Pendleton and LaGrande wagon road, N.W.
40.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S on W. face.
60.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. cor.; dug pits 18 x 18 x 12 ins. N and S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2