

## Subdivisions, T. 2 N., R. 33 E.

Chains		
	Variation 21° East..	
10.00	Gulch S.W.	
15.55	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W face.	
20.00	Canyon S.W.	-200
31.50	Top hill and begin descent.	+200
35.55	Set basalt stone 9 x 8 x 7 ins.. 6 ins. in the ground for ¼ sec. cor., marked ¼ on W. face; dug pits 18 x 18 x 12 ins. N & S of stone, 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it.	
43.55	Bottom hill and enter river, bottom.	
55.55	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake, 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W face.	
64.50	Stream 20 lks. wide runs W.	
66.00	Enter timber.	
75.55	Corner to secs. 4, 5, 8 and 9. Land, bottom and upland. Soil, 2nd rate in bottom; 1st rate on upland. Timber: Balm along river.	
North between secs. 31 and 32.		
	Variation 19½° East.	
16.25	Spring branch 3 lks. West.	
16.75	Wagon road W.	
20.00	Drove charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on W face.	