

## Subdivisions, T. 2 N., R. 33 E.

Chains	
	<p>long, 2 ins. square 12 ins. in the ground, marked T2N S20 on N.E; R33E S29 on S.E.; S30 on S.W. and S19 on N.W. faces, with 2 notches on S. and 5 notches on E. edges.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p> <p>Good agricultural land.. But little grass.</p>
	<hr/> <p>East on random between secs. 20 and 29.</p> <p style="text-align: right;">Variation 20° East. .</p> <p>Set temporary corners at 20, 40 and 60 chains, and at</p>
79.60	<p>Intersect N &amp; S line 4 lks. N of cor. to secs. 20, 21, 28 and 29.</p> <p style="text-align: center;">Thence</p> <p>N. 89° 58' W. on true line.</p> <p style="text-align: right;">Variation same.</p>
19.90	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E &amp; W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins in the ground marked 1/16 S on N face.</p>
24.75	<p>Tudie Willows creek 5 lks W.</p>
36.50	<p>Wagon road N.</p>
39.80	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. corner; dug pits 18 x 18 x 12 ins. E &amp; W of stake, 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked ¼ S on N face.</p>
59.70	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E &amp; W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.</p>
79.60	<p>Corner to secs. 19, 20, 29 and 30.</p> <p>Land, level. Soil, good. All fair agricultural land.</p>