

| Chains | |
|--------|---|
| 20.00 | <p>West on true line between secs. 19 and 30. Variation 20° East.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor; dug pits 18 x 18 x 12 ins. E and W of stake, 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16S on N face.</p> |
| 40.00 | <p>Deposited charred stake 12 ins. in the ground for 1/2 sec. corner; dug pits 18 x 18 x 12 ins. E and W of stake, 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/2S on N face.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E and W of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long</p> |
| 60.00 | <p>2 ins. square, 12 ins. in the ground marked 1/16 S on N face.</p> <p>Intersect W. bdy. Township and deposited charred stake 12 ins. in the ground for closing corner to secs. 19 and 30, 184 lks. N of cor. to secs. 24 and 25 T2 N.R. and 32 East; dug pits 18 x 18 x 12 ins. N.E. and S. of stake 5 1/2 ft. distant; raised mound of earth 2 ft. high, 4 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked C.C.T2N.R.33 E. on E.; S19 on N and S30 on S faces with 2 notches on S and 4 notches on N edges.</p> <p>Level land; soil, 1st rate. Some bunch grass.</p> |
| 76.25 | <p>North between secs. 19 and 20.</p> <p>Variation 20° East.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high,</p> |