

| Chains | |
|--------|---|
| 2.00 | Wagon road N. |
| 11.00 | Wagon road N. |
| 19.95 | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake, 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face. |
| 39.90 | Deposited charred stake 12 ins. in the ground for 1/4 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/8 S on N face. |
| 46.50 | Fence and enter field. |
| 48.00 | Dry ditch N.W. |
| 59.85 | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake, 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked 1/16 S on N face. |
| 79.80 | Cor. to secs. 17, 18, 19 and 20. Land, level. Soil, 1st rate. Well adapted to agriculture. |
| 20.00 | West on true line between secs. 18 & 19. Variation 19° East. Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face; Fence and leave field N & S. |
| 30.00 | Wagon road N. |
| 35.50 | Deposited charred stake 12 ins. in the ground for 1/4 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake, 5 1/2 ft. |
| 40.00 | Deposited charred stake 12 ins. in the ground for 1/4 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake, 5 1/2 ft. |