

## Subdivisions, T. 2 N., R. 33 E.

Chains	
	square 12 ins. in the ground marked $\frac{1}{4}$ S on N face.
43.75	Wagon road N & S.
59.70	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
74.00	Wagon road.
79.60	Cor. to secs. 7, 8, 17 and 18. Land, rolling. Soil, 1st rate.
West on true line between secs. 7 & 18. Var. $20\frac{1}{2}^{\circ}$ East.	
17.00	Gulch N.
20.00	Drove charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
40.00	Drove charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S on N face.
50.76	Gulch N.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
64.25	Pendleton and LaGrande wagon road.
70.25	Old Emigrant wagon road N.W.
76.75	Intersect W bdy. Township 395 links N of cor. to secs. 12 and 13 T2 N.R. 33 E. and deposited charred stake

-100