

Subdivisions, T. 2 N., R. 33 E.

Chains	<p>base over it and in N. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on W. face.</p> <p>71.50 Umatilla river, 80 lks., runs W.</p> <p>75.50 Cor. to secs. 5, 6, 7 and 8.</p> <p>Land, rolling hills. Soil, 1st and 2nd rate.</p> <p>Bunch grass short.</p> <p>The N$\frac{1}{2}$ of sec. 5 can be cultivated.</p> <p style="text-align: right;">Aug. 31st, 1887.</p>
	<p>General Description</p> <p>This Township is rough and mountainous only in secs. 36 & 25. The balance is rolling or level. The soil is a light loam, very little in cultivation. Grass is about killed out by stock.</p> <p>The Umatilla River runs from E. to W. across the N. portion of Township. Some level land along the river with high hills or bluffs on N. side. Considerable Balm timber and thorn brush along river bottom.</p>
	<p>Sub-Subdivisions of T. 2 N.R., 33 E.</p>
	<p>East through center of sec. 25.</p> <p style="text-align: right;">Variation 19° East.</p> <p>Commencing at $\frac{1}{4}$ sec. cor. bet. secs. 25 and 26. Set temporary corners at 20, 40 and 60 chains and at</p> <p>79.75 Intersect E. boundary Township at $\frac{1}{4}$ sec. cor. between secs. 25 and 30.</p> <p style="text-align: center;">Thence</p> <p>West on true line.</p> <p style="text-align: right;">Variation same.</p>
	<p>19.94 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake 5$\frac{1}{2}$ ft. dist.; raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>