

| Chains   |   |      |
|--|---|------|
| 39.94  | Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E and W of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face. |      |
| 53.00  | Wagon road, course N.W. and S.E.  |      |
| 59.91  | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face. |      |
| 62.00  | Gulch, course N.  | -100 |
| 71.00  | Top of ridge, course N.   | +250 |
| 79.88  | 1/16 sec. cor. between secs. 25 and 26.<br>Land, hilly and rolling.<br>Soil, 1st rate.  |      |
| East on random through S½ of sec. 24.                                  |   |      |
| Variation 19½° East.   |   |      |
| Commencing at 1/16 sec. cor., 20 chains N. of S.W. cor. of sec. 24 and |   |      |
| Set temporary corners at 20, 40 and 60 chains and at                   |   |      |
| 79.85  | Intersect E. bdy. Township 10 lks. N. of 1/16 sec. cor. between secs. 24 and 19.  |      |
| Thence,  |   |      |
| N. 89° 56' W. on true line.  |   |      |
| Variation same.  |   |      |
| 3.00   | Fence and enter field N and S.  |      |
| 19.96  | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked                 |      |