

## Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	<p>5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/4 S. on N. face.</p>
59.93	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ins. square, 2 ft. long, 12 ins. in the ground marked 1/16 S. on N. face.</p>
79.90	<p>1/16 sec. corner between secs. 23 and 24. Land, level. Soil, 1st rate. Grass poor.</p>
	<hr/> <p>East on random through N½ of sec. 24. Variation 20° East. Commencing at 1/16 sec. cor. 20 chains N. of ¼ sec. cor. between secs. 23 and 24. Set temporary corners at 20, 40 and 60 chains and at</p>
80.00	<p>Intersect E. boundary sec. at 1/16 sec. corner, Thence West on true line.</p>
12.00	<p>Variation 21° East. Gulch, course N.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>