

Chains	
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist. and raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
80.00	1/16 sec. corner between secs. 23 and 24. Land, mostly level. Soil, 1st rate.
79.92	East on random through S 1/2 of sec. 13. Variation 20-3/4° East. Beginning at 1/16 sec. cor. between secs. 13 and 14, 20 chains N. of S.W. corner to sec. 13, Set temporary corners at 20, 40 and 60 chains, and at Intersect E. bdy. of sec. 10 lks. N. of 1/16 sec. corner, Thence N. 89° 56' W. on true line.
19.98	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
21.75	Wagon road, course N and S.
30.85	Enter Indian field N. and S.
37.50	Branch 2 lks., course N.
39.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
51.00	Leave Indians field N and S.