

Sub-Subdivisions, T. 2 N., R. 33 E.

| Chains  |  |
|---|--|
| 59.94   | Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face. |
| 65.00   | Wagon road, course N.  |
| 79.92   | 1/16 sec. corner between secs. 13 and 14.<br>Land, mostly level; soil, good, partly cultivated.  |
| <hr/> East on random through center of sec. 13.       |  |
| Variation 20½° East.                                  |  |
| Commencing at ¼ sec. corner between secs. 13 and 14   |  |
| Set temporary corners at 20, 40 and 60 chains, and at |  |
| 79.88   | Intersect E. bdy. of sec., 12 lks. N. of ¼ sec. cor.   |
| Thence  |  |
| N. 89° 55' W. on true line.                           |  |
| Variation same.                                       |  |
| 19.97   | Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.    |
| 39.94   | Deposited charred stake 12 ins. in the ground for ¼ sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5½ ft. dist.; raised mound of earth 1-1/2 feet high, 3-1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S. on N. face. |
| 41.75   | Wagon road N.W.  |
| 47.00   | Creek, course N.   |
| 59.91   | Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in East pit drove stake 2 ft.   |