

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	<p>dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked <math>1/16</math> S on N. face.</p>
79.75	<p><math>1/16</math> sec. cor. between secs. 13 and 14. Land, rolling. Soil, 1st rate.</p>
	<p>East on random through <math>S\frac{1}{2}</math> of sec. 12. Variation <math>20^{\circ}</math> East..</p>
	<p>Commencing at <math>1/16</math> sec. cor. between secs. 11 and 12, 20 chains N. of <math>\frac{1}{4}</math> sec. corner.</p>
	<p>Set temporary sec. corners at 20, 40 and 60 chains and at</p>
79.80	<p>Intersect E. boundary sec., 8 lks. N of corner. Thence N. <math>89^{\circ} 57'</math> W. on true line.</p>
	<p>Variation same.</p>
19.95	<p>Set post 3 ft. long, 3 ins. square 24 ins. in the ground marked <math>1/16</math> S. on N. face for <math>1/16</math> Sec. cor.; dug pits 18 x 18 x 12 ins. E and W of post <math>5\frac{1}{2}</math> ft. dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base around post.</p>
39.90	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for <math>1/16</math> sec. cor., marked <math>1/16</math> S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post <math>5\frac{1}{2}</math> ft. dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base around post.</p>
53.60	<p>Enter field and pasture N. and S.</p>
58.00	<p>Wagon road, course N.E.</p>
59.85	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for <math>1/16</math> sec. corner, marked <math>1/16</math> S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post <math>5\frac{1}{2}</math> ft. dist. and raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base around post.</p>
79.80	<p>To beginning cor. Land, rolling. Soil, good. Grass, fair. The remainder of sec. 12 is unfit for agricultural purposes.</p>