

Chains	
39.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5 3/4 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 1/16 s on N. face.
59.85	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5 3/4 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 s on N. face.
79.80	To sec. cor. at place of beginning. Land, level. Soil, good.
79.80	East on random through center of sec. 26. Var. 20° East. Commencing at 3/4 sec. corner between secs. 26 & 27 Set temporary corners at 20, 40 and 60 chains and at Intersect E. boundary 4 lks. S. of 3/4 sec. corner. Thence S. 89° 58' W. on true line. Var. 19° East.
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 s on N. face.
20.75	Wagon road, course N.
39.90	Deposited charred stake 12 ins. in the ground for 1/4