

Chains	
59.94	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove a stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
79.92	<p>To 1/16 sec. corner, place of beginning. Land, level. Soil, good. Not cultivated.</p>
79.90	<p>East on random line through S 1/2 of sec. 23. Var. 20° East. Commencing at 1/16 sec. corner 20 chains N of S.W. cor. of sec. 23. Set temporary corners at 20, 40 and 60 chains, and at Intersect E. bdy. of sec. 7 lks. N. of 1/16 sec. corner between secs. 23 and 24. Thence N. 89° 57' W. on true line.</p>
19.97	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
39.95	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
59.92	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>