

Chains	
80.00	East on random through $N\frac{1}{2}$ of sec. 23. Variation 20° East. Commencing at 1/16 sec. cor., 20 chains North of $\frac{1}{4}$ sec. cor. between secs. 22 and 23. Set temporary corners at 20, 40 and 60 chains, and at Intersect E. bdy. of sec. 7 lks. N. of 1/16 sec. cor. Hence N. 89° 57' W. on true line.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. East and West of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N.
40.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. East and West of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face. To 1/16 sec. corner, beginning place.
80.00	Land, level. Soil, 1st rate. Not cultivated.
	East on random through $S\frac{1}{2}$ of sec. 14. Variation 20° East. Commencing at 1/16 sec. corner 20 chains N. of S.W. cor. of sec. 14. Set temporary corners at 20, 40 and 60 chains and at