

Chains	
79.70	<p>To point of beginning. Land, level or bottom. Soil, generally good. Partly cultivated.</p>
79.80	<p>East on random through center of Sec. 2. Var. 20° East. Commencing at <math>\frac{2}{3}</math> sec. corner between secs. 2 and 3, Set temporary corners at 20, 40 and 60 chains, and at Intersect East bdy. 7 lks. N. of <math>\frac{2}{3}</math> sec. corner, Thence N. 89° 57' W. on true line. Var. same.</p>
19.95	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post <math>5\frac{1}{2}</math> ft. dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base around post.</p>
39.90	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground marked <math>\frac{2}{3}</math> sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of post <math>5\frac{1}{2}</math> ft. dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base around post.</p>
44.00	<p>Gulch, S.</p>
59.85	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of stake <math>5\frac{1}{2}</math> ft. dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base around post.</p>
79.80	<p>To point of beginning. Land, rolling. Soil, good. Not cultivated.</p>
	<p>East on random through N<math>\frac{2}{3}</math> of Sec. 2. Var. 21° East. Commencing at 1/16 sec. cor. 20 chains N. of <math>\frac{2}{3}</math> sec. cor. between secs. 2 and 3. Set temporary corners at 20, 40 and 60 chains, and at</p>