

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
59.85	<p>square 12 ins. in the ground marked 1/4 S. on N. face.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
79.80	<p>To point of beginning.</p> <p>Land, rolling.</p> <p>Soil, 1st rate. Partly cultivated.</p>
79.60	<hr/> <p>East on random through N½ of sec. 34.</p> <p style="text-align: right;">Variation 20° East.</p> <p>Commencing at 1/16 sec. cor. 20 chains N of ¼ sec. cor. Set temporary corners at 20, 40 and 60 chains, and at Intersect E. boundary 20 lks. N. of 1/16 sec. corner,</p> <p style="text-align: center;">Thence</p> <p>N.89° 51' W. on true line.</p> <p style="text-align: right;">Variation same.</p>
19.90	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
39.80	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
59.70	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft.</p>