

## Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	East on random through center of sec. 27.
	Variation 20° East.
	Commencing at $\frac{1}{4}$ sec. cor. between secs. 27 and 28,
	Set temporary corners at 20, 40 and 60 chains, and at
79.70	Intersect E. boundary 12 lks. N of $\frac{1}{4}$ sec. corner.
	Thence
	N. 89° 55' W on true line.
	Variation same.
19.93	Deposited charred stake 12 ins. in the ground for 1/16
	sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake
	5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft.
	base over it and in E. pit drove stake 2 ft. long, 2 ins.
	square, 12 ins. in the ground marked 1/16 S on N. face.
21.00	Gulch and dry ditch, course N.W.
39.85	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec.
	cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft.
	dist; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over
	it and in E. pit drove stake 2 ft. long, 2 ins. square
	12 ins. in the ground marked 1/4 S on N. face.
59.77	Deposited charred stake 12 ins. in the ground for 1/16
	sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake
	5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft.
	base over it and in E. pit drove stake 2 ft. long, 2 ins.
	square 12 ins. in the ground marked 1/16 S. on N. face.
79.70	To point of beginning.
	Soil, 1st rate.
	Land, level.
	East on random through N $\frac{1}{2}$ of sec. 27.
	Variation 20° East.
	Commencing at 1/16 sec. cor. 20 chains North of 1/4 sec.
	corner between secs. 27 and 28.
	Set temporary corners at 20, 40 and 60 chains, and at
79.80	Intersect E. boundary at 1/16 sec. cor.
	Thence
	West on true line.