

Chains	
19.95	Deposited charred stake 12 ins. in the ground for 1/16 S cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face. Variation same.
39.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins., E and W of stake, 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
40.00	Gulch, course N.
59.85	Deposited charred stake 12 ins. in the ground for 1/16
79.80	sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face. To place of beginning.
79.92	Land, level. Soil, good. Not cultivated.
19.98	East on random through S 1/2 of sec. 22. Variation 20° East. Commencing at 1/16 sec. cor. 20 chains N. of S.W. cor. of sec. 22. Set temporary cors. at 20, 40 and 60 chains, and at Intersect E. boundary of sec. at 1/16 sec. cor. Thence West on true line
19.98	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.