

Chains

80.00 cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face. Ditch and point of beginning. Land, level. Soil, 1st rate. Not cultivated.

East on random through N 3/4 of sec. 22. Var. 20° 10' East. Commencing at 1/16 sec. cor. 20 chains N of 3/4 sec. between secs. 21 and 22.

Set temporary corners at 20, 40 and 60 chains, and at

Intersect E. bdy. 20 lks. S, or 1/16 sec. cor.

Thence

S. 89° 51' West on true line.

Variation 20° East.

20.02 Deposited charred stake 12 ins. in the ground for 1/16 sec.

cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4

ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft.

base over it and in E. pit drove stake 2 ft. long, 2 ins.

square 12 ins. in the ground marked 1/16 S on N. face.

40.05 Deposited charred stake 12 ins. in the ground for 1/16

sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake

5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft.

base over it and in E. pit drove stake 2 ft. long, 2 ins.

square 12 ins. in the ground marked 1/16 S on N face.

60.07 Deposited charred stake 12 ins. in the ground for 1/16 sec.

cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4

ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft.

base over it and in E. pit drove stake 2 ft. long, 2 ins.

square 12 ins. in the ground marked 1/16 S on N face.

80.10 To point of beginning.

Land, level.

Soil, 1st rate.

Not cultivated.