

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
59.85	base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked 1/16 S on N face. Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
79.80	To point of beginning. Land, level. Soil, 1st rate.
79.84	East on random through center of sec. 10. Variation 21° East. Commencing at 3/4 sec. cor. bet. secs. 9 and 10 Set temporary corners at 20, 40 and 60 chains and at Intersect E. bdy. 7 lks. N. of 3/4 sec. cor. Thence N. 89° 57' W. on true line. Variation 20 3/4° East.
11.50	Indian House N of line.
17.50	Creek Dry and fence in brush.
19.96	Set post 3 ft. long, 3 ins. square 12 ins. in the ground marked 1/16 S on N. face for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of post 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base around post.
32.50	Fence N. and S.
39.92	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 3/4 sec. corner, marked 1/2 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist., and raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base around post.
48.00	Fence, course N.E.
52.00	Fence, course N.W.
59.88	Set basalt stone 14 x 12 x 10 ins., 10 ins. in the ground for 1/16 sec. corner, marked 1/16 on N. face; dug pits