

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	18 x 18 x 12 ins. E. and W. of stone $5\frac{1}{2}$ ft. dist.; raised mound of stone and earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
72.25	Wagon road, course N & S.
72.50	Fence, course N. & S.
79.84	To point of beginning. Land, mostly river bottom. Soil, 2nd rate. Some brush.
	Oct. 26th, 1887.
	East on random through $N\frac{1}{2}$ of sec. 10. Variation $20\frac{1}{2}^{\circ}$ East. Commencing at $1/16$ sec. corner 20 chains N. of $\frac{1}{4}$ sec. cor. between secs. 9 & 10, Set temporary corners at 20, 40 and 60 chains, and at 79.92 Intersect E. bdy. at $1/16$ sec. cor. Thence West on true line. Variation, same.
19.98	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $1/16$ sec. cor. marked $1/16$ S on N face, from which A birch 13 ins. diam. bears $N.45^{\circ} E.40$ lks. dist., marked $1/16$ S.B.T. A palm 18 ins. diam. bears $S.70^{\circ} W. 68$ lks. dist., marked $1/16$ S.B.T.
24.00	Leave brush.
39.96	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $1/16$ sec. cor., marked $1/16$ on N. face and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable.
40.70	Fence N and S.
59.94	Set basalt stone 12 x 8 x 5 ins., 8 ins. in the ground for $1/16$ sec. cor., marked $1/16$ on N. face and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
65.65	Wagon road N. and S. and