

Chains	
67.90	<p>Indian House bears N. 20° E. 300 lks. Fence N. and S.</p>
79.92	<p>To point of beginning. Land, mostly river bottom. Soil, 1st rate. Considerable brush and some timber, Balm &c.</p>
79.90	<p>East on random through $S\frac{1}{2}$ of sec. 3. Variation 20° East Commencing at 1/16 sec. corner 20 chains N of S.W. cor. of sec. 3. Set temporary corners at 20, 40 and 60 chains and at Intersect E. bdy. at 1/16 sec. cor. Thence West on true line Variation, same.</p>
16.00	<p>Fence, course N and S.</p>
19.98	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5$\frac{1}{2}$ ft. dist.; raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
39.95	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. cor., marked 1/16 S on N. face and raised mound of stone 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base around post.</p>
56.50	<p>Fence and enter field N. and S.</p>
59.94	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. cor., marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post 5$\frac{1}{2}$ ft. dist.; and raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base around post.</p>
79.90	<p>To point of beginning. Land, rolling. Soil, 2nd rate. Little grass.</p>