

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
40.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.
49.50	Wagon road, course N.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
66.00	Little Tудie Willows creek, 5 lks. N.W.
71.00	Leave same.
80.00	To point of beginning. Land, level. Soil, 1st rate.
<hr/>	
	East on random through center of sec. 33. Variation 20 1/2° East. Commencing at 1/4 sec. cor. between secs. 32 and 33 Set temporary corners at 20, 40 and 60 chains and at 79.95 Intersect E. bdy. sec. 10 lks. N of 1/4 sec. corner Thence N. 82° 56' W on true line Variation 20° East
19.98	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
25.75	Wagon road, course N.E.
39.97	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/4 sec. corner, marked 1/4 S on N. face; dug pits 18 x 18 x 12 ins. E. and W of stake 5 1/2 ft. dist.; raised