

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	Land, mostly level.
	Soil, 1st rate.
<hr/>	
	East on random through $N\frac{1}{2}$ of sec. 28.
	Variation 20° East.
	Commencing at $1/16$ sec. cor. 20 chains N of $\frac{1}{4}$ sec. cor. bet. secs. 28 and 29
	Set temporary corners at 20, 40 and 60 chains, and at
79.95	Intersect E. bdy. 17 lks. S of $1/16$ sec. cor.
	Thence
	S. $89^{\circ} 53'$ W on true line
	Variation same.
12.28	Wagon road N. and S.
16.50	Fence and enter field N and S.
19.99	Deposited charred stake 12 ins. in the ground for $1/16$ sec. cor.; dug pits 18 x 18 x 12 ins. E and W. of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $1/16$ S on N face.
21.75	Lane, course N.E.
39.97	Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins E and W of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $1/16$ S. on N. face.
59.96	Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $1/16$ S on N. face.
64.25	Cross creek dry and repeatedly cross same until at
69.00	Leave creek.